DATE:			FLUSH MOUNT HARD DUCT SUBMITTAL DATA FOR:						
COMPANY:			CARRIER UNITS						
			48/50PG16						
SUBMITTED BY:									
NOTES:									
ROOF CURB									
	TELY)	×				>			
DUCT SUPPORT									
(SUPPLIED WITH DUCT KIT)									
"A" "B"									
INSULATED SUPPLY AIR							1		
TRANSITION DUCT									
INSULATED RETURN AIR									
TRANSITION DUCT									
SUPPLY DUCT MUST BE									
FIELD SUPPORTED									
FEATURES:									
FLUSH MOUNT PAINTED WHITE DIFFUSER GRILLE WITH FIXED BLADES									
SUPPLY DUCT INSULA									
RETURN DUCT INSULATED WITH 1/2" INSULATION									
					1	ך 			
CAMBRIDGEPORT PART NUMBER	APPLICABLE CURB MODEL NUMBERS	"A"	"B"	DIFFUSER SIZE	return Grill	NOMINAL THROW IN CFM FT.			
1010441	CRRFCURB0034A00SL	54 1/4"	58 7/8"	48" X 48"	33" X 33"	6,000	MIN 28'	MAX 46'	
NOTES:							20	10	
<ul> <li>1 - DO NOT INSTALL FACTORY SUPPLIED DUCT SUPPORTS UNLESS NOTED IN ASSEMBLY INSTRUCTIONS</li> <li>2 - INSTALL CONCENTRIC DUCTWORK BEFORE SETTING A/C UNIT IN PLACE</li> <li>3 - PLACE GASKETING ON ALL SURFACES OF DUCT FLANGE AND CURB</li> <li>4 - ALIGN CARRIER UNIT SUPPLY OPENING TO MATCH SUPPLY OPENING OF CONCENTRIC DUCT KIT</li> <li>5 - FIELD BAFFLES MAY BE REQUIRED FOR BALANCING</li> <li>6 - FOR INSTALLATION SEE ASSEMBLY INSTRUCTIONS</li> </ul>									
Drawn By: CRF Date: 2/13/08 Rev: 0				PI	SALISBURY, MA 01952 PHONE 1-800-648-2872 FAX 978-462-9189				